




E-ELT Optomechanics Status Overview




Belgian ESO Industry Day
June 18th, 2015

Marc Cayrel
E-ELT Optomechanics Project Manager

E-ELT Optomechanics




M1 Unit
 39-m
 Concave – Aspheric f/0.9
 Segmented (798 Segments)
 Active + Segment shape Control



M2 Unit
 4-m
 Convex Aspheric f/1.1
 Passive + Position Control




M3 Unit
 4-m – Concave – Aspheric f/2.6
 Active + Position Control





M4 Unit
 2.4-m
 Flat
 Segmented (6 petals)
 Adaptive + Position Control



M5 Unit
 2.7x2.1-m
 Flat
 Passive + Fast Tip/Tilt




LGSU
 (Laser Guide Star Units)
 Laser Sources + Laser Beacons
 shaping and emitting



39-m diameter
 6 x 133 segments (1.4-m)
 1 x 133 spare segments
 Total: 931 segments

M1 Mirror	
Outer diameter (mm)	39146.0
Inner diameter (mm)	9418.4
M1 Optical Prescription	
Radius of curvature (mm)	68685
Conic constant	-0.9964064



931 x M1 Segments

931 x Blanks + 19 x Spare Blanks
931 x Segments Polishing

4530 x M1 Edge Sensors

4530 x Sensors + 813 x Electronics + Spares
(100 sensors – 15 x controllers)

931 x M1 Segment Supports

& SA Auxiliary Equipment
[SA Handling Tools, SA Transport Containers, SA AIV Tools]


2394 x M1 Position Actuators

2394 x Actuators + 798 x Electronics + Spares
(16 x PACT – 6 x Controllers)

M1 Auxiliary Equipment

Aux. Sensors, Mass Dummies, Carts, Stands, Manipulator, Phasing Gun, Alignment Tools

Segment Assembly



Subcell



**Including glass, mechanics, electronics:
⇒ more than 10 000 components**

M1 Unit – Segment Supports


931 x M1 Segment Supports

798 x M1 Fixed Frames


3 x M1 SA Handling Tools

798 x M1 SA Transport Containers


1 x M1 SA AIV Tools




Segment Support




Fixed Frame




Prototype Segment Support



Prototype Fixed Frame



Extraction & Handling



Prototype Transport Container




AIV Tooling



Handling Tool

M1 Unit - Segment Supports

M1 Segment Support – Procurement





M1 Unit - Segment Supports

M1 Segment Support – Procurement

Final Design and qualification: awarded, 2 contracts ongoing.

VDL/TNO Eindhoven/Delft (The Netherlands)

◆ Kick Off: 26.01.15

CESA Madrid (Spain)

◆ Kick Off: 10.02.15



M1 Unit - Segment Supports

M1 Segment Support – Procurement

Final Production:


CfT: planned in May 2017

Contract start: June 2018

Production plan: 2.5 years

Required Skills:

- Precision Mechanical Manufacturing and Integration
- Mass Production



M1 Unit – Blanks and Polishing


**931 x Grind & Pre-Polish
Segment Roundels**

931 x Bound interfaces

**931 x Cut to hexagonal
shape**


**931 x Integrate with
Segment Support**

**931 x Finish figure and
Test Segment
Assemblies**




M1 Unit - Blanks and Polishing

- RFI for blanks procurement: ongoing.
- RFI for Polishing: completed.
- PI for Polishing: July 2015.
- CfT for Polishing: planned Nov 2015




Pads Bonding



CNC - Cutting



Support integration



Ion Figuring

Polishing #2



Blanks



High Precision grinding



Stressed Mirror Polishing



Bonnet Polishing and Lapping



Polishing #1



Pre-Polished Roundel



M1 Unit – Blanks and Polishing

M1 Segments Polishing – Procurement


CfT: planned in Nov 2015

Contract start: Jan 2017


Contract plan: 7 years

Required Skills:


- High Performance optomechanical components manufacturing, integration, and testing
- Mass Production



M1 Unit – Edge Sensors



**4630 x M1 Edge Sensors
(Including 100 Spares)**




**813 x Controllers & Electronics
(Including 15 Spares) – One for 6
Sensors**

**Dummy Masses
To equip M1 free edges
For figuring**

M1 Unit – Edge Sensors

M1 Edge Sensors – Procurement



M1 Unit – Edge Sensors

M1 Edge Sensors – Procurement


CfT: planned in Jan 2016

Contract start: Jan 2017

Production plan: 5 years

Required Skills:

- Precision non-contact sensors (inductive, nm precision)
- A/D electronics, mechanics
- Control
- Mass Production




M1 Unit – Position Actuators

2 Stage actuators – nm precision along 15 mm stroke.

2 Technologies still competing:

Hard PACTs (Piezzo) / Soft PACTs (voice coil)




**2410 x Position Actuators
(Including 16 Spares)**

**804 x Controllers & Electronics
(Including 6 Spares)
3 Channels**

M1 Unit – Position Actuators

M1 Position Actuators – Procurement



M1 Unit – Position Actuators

M1 PACTs – Procurement


CfT: planned in Apr 2016

Contract start: Jun 2017

Production plan: 6.5 years

Required Skills:

- High precision actuators (nm)
- Electro-Mechanics, Electronics
- Control
- Mass Production




Passive 4-m f/1.1 convex mirror, highly aspheric (+ warping harness provision)

Axial support: 18 points whiffletree + tripods

Lateral support: 12 tangential struts + fixed lateral and clocking

Positioning system: hexapod with sub-micron accuracy

Earthquake protection: mirror restrainers + load limiters











Active 4-m f/2.6 concave mirror, mild aspheric (warping harness shape control)

Axial support: 18 points whiffletree + tripods

Lateral support: 12 tangential struts + fixed lateral and clocking

Positioning system: hexapod with sub-micron accuracy

Earthquake protection: mirror restrainers + load limiters



M2 and M3 /Units are very similar ones !

⇒ Same size, same support concept

⇒ Same mass, same stiffness

⇒ Same shaping system (warping harness: provision on M2, required on M3)

⇒ Same positioning system


⇒ Common auxiliary equipment (handling, transport, ...)

Main difference: the mirrors.




Hence, ESO is willing to contract:

- The M2 Mirror
- The M3 Mirror
- The M2+M3 Cells


M2 Mirror – Procurement



M3 Mirror – Procurement



M2 & M3 Cells – Procurement



M2 Mirror – Procurement


CfT: planned in Oct 2015

Contract start: Jun 2016

Production plan: 5.5 years

Required Skills:

- High performance large optics manuf. & testing
- Optics, Mechanics, Metrology, Adhesive bonding, ...



M3 Mirror – Procurement

CfT: planned in Feb 2016


Contract start: Jan 2017

Production plan: 4.5 years

Required Skills:

- High performance large optics manuf. & testing
- Optics, Mechanics, Metrology, Adhesive bonding, ...

Activity Desc.	Duration	Early Start	Early Finish
M3 Mirror - Procurement	442d	03Mar2015	11Nov2016
M3 Mirror - RFI - Advance Info	0	03Mar2015	03Mar2015
M3 Mirror - Synopsis	0	03Jul2015	03Jul2015
M3 Mirror - RFI - ILOs	20d	03Jul2015	30Jul2015
M3 Mirror - Synopsis and Draft SPE	0	31Jul2015	31Jul2015
M3 Mirror - RFI - Industry	45d	03Aug2015	02Oct2015
M3 Mirror - RFI - Clarifications	30d	05Oct2015	13Nov2015
M3 Mirror - PI Documentation	30d	05Oct2015	13Nov2015
M3 Mirror - PI	25d	16Nov2015	18Dec2015
M3 Mirror - Finalize CfT Package	29d	21Dec2015	29Jan2016
M3 Mirror - Tendering	90d	01Feb2016	03Jun2016
M3 Mirror - Bids Clarifications and Evaluation	60d	06Jun2016	26Aug2016
M3 Mirror - Selection - CAC	10d	29Aug2016	09Sep2016
M3 Mirror - FC Documentation	20d	12Sep2016	07Oct2016
ESO FC Approval - M3 Mirror	0	11Nov2016	11Nov2016
M3 Mirror - Manufacturing Contract	1149d	06Jan2017	09Jun2021





M2&M3 Cells

M2&M3 Cells – Procurement

CfT: planned in Feb 2016

Contract start: Jan 2017


Production plan: 4.5 years

(schedule shall read M2 and/or M3)






Required Skills:


- Optomechanics, Mechanics (for large high performance optics)
- Electromechanics (warping harness)
- Mechanical & optomechanics integration and testing

Activity Desc.	Duration	Early Start	Early Finish
M2 Cell - Procurement	450d	19Feb2015	11Nov2016
M2 Cell - RFI - Advance Info	0	19Feb2015	19Feb2015
M2 Cell - RFI - Synopsis	0	03Jul2015	03Jul2015
M2 Cell - RFI - ILOs	20d	06Jul2015	31Jul2015
M2 Cell - Synopsis and Draft SPE	0	31Jul2015	31Jul2015
M2 Cell - RFI - Industry	45d	03Aug2015	02Oct2015
M2 Cell - RFI - Clarifications	30d	05Oct2015	13Nov2015
M2 Cell - PI Documentation	30d	05Oct2015	13Nov2015
M2 Cell - PI	25d	16Nov2015	18Dec2015
M2 Cell - Finalize CfT Package	29d	21Dec2015	29Jan2016
M2 Cell - Tendering	90d	01Feb2016	03Jun2016
M2 Cell - Bids Clarifications and Evaluation	60d	06Jun2016	26Aug2016
M2 Cell - Selection - CAC	10d	29Aug2016	09Sep2016
M2 Cell - FC Documentation	20d	12Sep2016	07Oct2016
ESO FC Approval - M2 Cell	0	11Nov2016	11Nov2016
M2 Cell - Manufacturing Contract	1160d	09Jan2017	24Jun2021




- 2.4-m flat adaptive mirror – 6 petals
 - Preliminary Design Study contract completed
 - Contract for Final Design and Manufacturing being awarded
 - Contract for Optics being awarded
 - Contracts start: July 2015
- ⇒ Check ESO Web site to know contractors







M5 Mirror



M5 Electromechanical Subunit



Prototype Actuator



M5 Local Control System






Scale 1 Prototype Unit


M5 Auxiliary Equipment [Shipping, Handling, AIV]

Spare Parts

M5 Mirror – Procurement



M5 EMU – Procurement



M5 Mirror – Procurement


CfT: planned in July 2017

Contract start: July 2018

Production plan: 4 years

- Required Skills:**
- High performance large optics manuf. & testing
 - Optics, Mechanics, Metrology, Adhesive bonding, ...

Activity Desc.	Duration	Early Start	Early Finish
M5 Mirror	1160d	07Jul2017	22Dec2021
M5 Mirror - Procurement	220d	07Jul2017	11May2018
M5 Mirror - Tendering	120d	07Jul2017	21Dec2017
M5 Mirror - Selection	60d	22Dec2017	15Mar2018
M5 Mirror - Prepare FC Documentation	20d	16Mar2018	12Apr2018
M5 Mirror - FC Approval	0	11May2018	11May2018
Phase 1 - Design M5 Mirror	160d	05Jul2018	15Feb2019
Phase 2 - Manufacture M5 Blank	640d	27Sep2018	17Mar2021
Phase 3 - Mirror Finishing	500d	21Jan2020	22Dec2021
M5 Delivery (Stays at polisher facilities)	0	22Dec2021	22Dec2021



M5 EMU – Procurement


CfT: planned in Jan 2018

Contract start: Jan 2019

Production plan: 3.5 years

Required Skills:

- Optomechanics, Mechanics (for large high performance optics)
- Electromechanics
- Mechanical & optomechanics integration and testing
- Control





Prefocal Stations

Interface with Telescope have changed.


⇒ Under development...

⇒ See Roberto's presentation






Laser Guide Star Units




Toptica 20W VLT AOF Laser Source



Laser Source

Projector



Laser Source Control Electronics

6 +1 Laser Sources
 (Including 1 Spare)
 20/25W Raman Fiber Amplifier

Local Electronics and Control System

Auxiliary Equipment
 (AIV, handling, shipping, testing)


- 6 Laser Beam Projection Subunits**
- Mechanical Structure & enclosure
 - Beam relay and diagnostics
 - Launch Telescope
 - Baffle towers
 - Cooling
 - Control Electronics



TNO 20W VLT AOF Launch Telescope


Laser Guide Star Units

Laser Sources – Procurement



Laser Guide Star Units

Laser Beam Projection Subunits – Procurement



Laser Guide Star Units

Lasers – Procurement


CfT: planned in Jan 2018

Contract start: Jan 2019

Production plan: 4 years

Required Skills:

- High power lasers 589 nm





Laser Guide Star Units

LBPS – Procurement

CfT: planned in Jan 2018


Contract start: Jan 2019

Production plan: 4 years

Required Skills:

- Optomechanics, Mechanics
- Electromechanics
- Mechanical & optomechanics integration and testing
- Control

Activity Desc.	Duration	Early Start	Early Finish
Laser Beam Projection Subunits	1460d	23Jun2017	02Feb2023
Laser Beam Projection Subunits - Procurement	360d	23Jun2017	09Nov2018
Laser Beam Projection Subunits - Technical and Managerial	120d	23Jun2017	07Dec2017
Laser Beam Projection SubUnits - Tendering	120d	08Dec2017	24May2018
Laser Beam Projection SubUnits - Selection	60d	22Jun2018	13Sep2018
Laser Beam Projection SubUnits - Prepare FC Documentation	20d	14Sep2018	11Oct2018
Laser Beam Projection SubUnits - FC Approval	0	09Nov2018	09Nov2018
Laser Beam Projection Subunits (LGSU) - Manufacture (Phase 1)	1100d	09Nov2018	02Feb2023





E-ELT Optomechanics - Conclusion

WE ARE DOING IT NOW !!!

PLEASE JOIN 😊 !!!